OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, HASSAN.

Brief Notification dated 10th September 1953.

Sealed tenders in triplicate superscribed as "Tender for providing Electric Lights to the Assistant Superintendent of Lines' Quarters and Transmission Line Inspector's Quarters (of B.B.T. Lines) at New Electric Colony near Master Unit Sub-Station, Tiptur", will be received in the Office of the Superintendent, Power and Lighting, Hassan, up to 4 P.M. on Wednesday, the 30th September 1953.

Intending tenderers are requested to apply to this office for copies of details of specification. Detailed sketch and plan may be seen at any time in the Office of the Superintendent, Power and Light, Hassan, on working days between 11 A.M. and 5 P.M.

The earnest money required along with tender is Rs. 56-8-0. Specific rate should be given for each item in the schedule and the rates should be noted both in words and figures.

The tendered rate should be for work to be done as per standard specifications approved by the Department and for using the best quality of materials.

The works should be completed in all respects within fifteen days from the date of acceptance of the tender.

The quantities as estimated are only approximate and are liable to alterations, omissions, deductions, or additions at the discretion of the officers of the Department. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

The right of rejection of any or all the tenders without assignment of any reason therefor, rests with the undersigned.

Within 8 days (eight days) of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the Departmental schedule contract form for the due fulfilment of the contract.

The successful tenderer will have to pay 5 per cent of the estimated amount towards Security Deposit before executing the agreement at the time of awarding the work.

Providing Electric Lights to the Assistant Superintendent of Lines' Quarters at New Electric Colony, Tiptur.

No.	Names of materials, etc.	Unit	Quantity.	Rate R. as. p.	Amount Rs. as. p.
1	Supplying and fixing and wiring the mains in 5/8" heavy guage braized conduit pipe using No. 7/·029 insulated wire 600 V. grade from Government pole to the meter board with necessary accessories such as stout clamps, bends, etc., complete.	R.ft.	25	...	...
2	Supplying, fixing and wiring T.W. Meter board 18"×15"×1" with 2" batten alround and ½" rear board treated with two coats of varnish using No. 7/·029 insulated wire 600 volts grade for main circuit equipping the same with 10 amp. DPST ironclad switch with fuse arrangements complete.	No.	1	...	...
3	Supplying, fixing and wiring in 2"×1" T.W. 2-way casing and capping treated with two coats of varnish using No. 7/·029 600 V. grade insulated wire for main circuit and No. 3/·036 wire insulated 600 V. grade for drop lights complete with high grade ceiling roses flexible silk chord, polished brass holder B.C. and 5 amps, superior foreign make control switch, 60 Watts Clear B.C. 250 V. lamps and other accessories, etc., complete.	No.	7	...	...
4	Do do for swan-neck polished brass brackets 9"×5/8" with stout bottom B.C. lamp holder and 5 amp foreign make control switch, 60 Watts Clear B.C. 250 V. lamps and necessary accessories, etc., complete.	No.	4	...	...
5	Do do superior make water-tight fittings complete with 5 amp. superior (English or American) foreign make control switch, 60 Watts Clear B.C. 250 V. lamps and other accessories, etc.	No.	1	...	...
6	Do do for superior make (English or American) bulk-head fittings 12" with B.C. P.B. Holder and 5 amp. foreign make superior control switch with 60 Watts Clear 250 V. B.C. lamps.	No.	1	...	...
7	Do do for 5 amps. porcelain base combined wall plug with pin and switch best foreign make, wiring with No. 7/·029 insulated wire 600 V. grade mounted on suitable wooden block with all necessary accessories.	No.	4	..	...
8	(a) Supplying fixing tin enamelled shades 10"×5½"	No.	5	...	...
	(b) Do white opal glass shades 8"	No.	6	...	...
9	Supplying, fixing and earthing the conduit pipe, iron clad switch using No. 6 B. and S. tinned copper wire and 12"×12"×1/8" tinned copper plate as per departmental rules.	No.	L.S.	...	...
10	Do twin conductors lead cable No. 14 B. and S. using messenger wire to the horse stables providing 5 amp. fuse out-out at the main building and providing a bracket with 14 B. and S. wire insulated switch and lamp 60 watts 250 V. complete with shades.	No.	1	...	...

Providing Electric Lights to the Transmission Line Inspector's Quarters (of B.B.T. Lines) at New Electric Colony near Master Unit Sub-Station, Tiptur.

No.	Names of materials, etc.	Unit	Quanity.	Rate Rs. as. p.	Amount Rs. as. p.
1	Supplying, fixing and wiring the mains in 5/8" heavy guage braized conduit pipe using No. 7/·029 insulated wire 600 V. grade from Government pole to the meter board with necessary accessories such as stout clamps, bends, etc., complete.	R.ft.	25	...	...
	Supplying, fixing and wiring T.W. meter board 18"×15"×1" with 2" batten alround and ½" rear board treated with two coats of varnish using No. 7/·029 wire insulated 600 V. grade for the main circuit equipping the same with 15 amp. D.P.S.T. iron clad switch with fuse arrangements, complete.	No.	1	...	...
	Supplying, fixing and wiring in 2"×1" T.W. two-way casing and capping treated with two coats of varnish using No. 7/·029 wire insulated wire 600 V. grade for mains and No. 3/·036 insulated wire 600 V. grade for circuits and drop lights complete with high grade bakelite ceiling roses, flexible silk cord, polished brass B.C. holder and 5 amp. superior foreign make control switch, 60 Watts Clear B.C. 250 V. lamps and other accessories, etc., complete.	No.	6	...	...
4	Do do batten holders mounted on T.W. round block with 5 amp. superior foreign make control switch, 60 Watts Clear B.C. 250 V. lamp and other necessary accessories, etc., complete.	No.	1	...	...
5	Do do for water tight fittings (English or American) complete with 5 amp. superior foreign make control switch 60 Watts Clear B. C. 250 V. lamp and other accessories, etc., complete.	No.	1	...	...
6	Do do for superior make (English or American) bulk-head fitting 12" with B.C. P.B. holder and 5 amp. superior foreign make control switch with 60 W. clear B.C. 250 V. lamps and other accessories, etc., complete.	No.	1	...	...
7	Do do for 5 amp. porcelain base combined wall plug with pin and switch, best foreign make, wiring with No. 14 B. and S. wire insulated 600 V. grade mounted on suitable wooden block with all necessary accessories, etc., complete.	No.	2	...	...
8	Supplying, fixing tin enamelled shades 10"×5½"	No.	7	...	...
9	Supplying, fixing and earthing the conduit pipe, iron clad switch using No. 6 B. and S. tinned copper wire and 12"×12"×1/8" tinned copper plate as per departmental rules.	No.	1	...	...

977

K. N. RANGASWAMY, *Superintendent.*

OFFICE OF THE DISTRICT LOCK-UP OFFICER, SHIMOGA.

Abstract Notification dated 4th September 1953.

Notice is hereby given that sealed tenders in quadruplicate typed or clearly written in ink on half sheet foolscap size paper will be received in the Office of the District Lock-up Officer at 9-30 A.M. on Tuesday the 6th October 1953, by the District Lock-up Officer, Shimoga, for the supply of ration and other articles required for the use of the prisoners confined in the District Lock-up at Shimoga from 1st January 1954 to end of December 1954. No tender will be received unless accompanied by a deposit in treasury receipt only, equal to not less than 5 per cent of the total value of the tender. The tender deposit to be made will be to the nearest next thousand.

Detailed information or the printed tender notification may be obtained in the above office during working hours.

T. L. N. PANDIT,

4052 *Dist. Lock-up Officer.*